Iran J Orthod. 2023 December; 18(2):e1137. doi: 10.22034/ijo.2023.2015817.1137.
Published online 2023 December 1
Research Article **Open Access**

Relationship of Upper Pharyngeal Airway Volume and Tongue Position in Different Skeletal Patterns: A CBCT Study

Kazem Dalaie [1], Shabnam Dadkhah [2], Mohammad Behnaz [1], Yaser Safi [3], Soodeh Tahmasbi [1], Yasamin Vazirizadeh [4*]

[1] Associate Professor, Department of Orthodontics, School of Dentistry, Shahid Beheshti University of Medical Sciences, Tehran, Iran
[2] Dentist, Private Practice, Tehran, Iran
[3] Associate Professor, Department of Oral and Maxillofacial Radiology, School of Dentistry, Shahid Beheshti University of Medical Sciences, Tehran, Iran
[4] Resident, Department of Orthodontics, School of Dentistry, Shahid Beheshti University of Medical Sciences, Tehran, Iran

***Corresponding Author:** Yasamin Vazirizadeh

Address: Department of Orthodontics, School of Dentistry, Shahid Beheshti University of Medical Sciences, Velenjak St., Shahid Chamran Highway, Tehran, Iran.
E-mail: yasivaziri74@gmail.com

Received: 2023 August 16; **Revised:** 2023 November 21; **Accepted:** 2023 November 27

Abstract

Aim: This study assessed the relationship of upper pharyngeal airway volume with tongue position in different sagittal and vertical skeletal patterns using cone-beam computed tomography (CBCT).
Methods: CBCT images of 225 participants (149 females and 76 males) over 18 years of age were evaluated in three groups with sagittal Class I, II, and III skeletal patterns. Class I and II individuals were subdivided into three vertical subgroups: high angle, normal, and low angle. The CBCT scans were evaluated three-dimensionally, and the volume of the lower nasopharynx (LNP), oropharynx (ORP), and velopharynx (VLP) was calculated in addition to the total upper pharyngeal airway volume (TV). The tongue position (according to Graber's analysis and D1-D5 and D1'-D5' lines) was determined, and the tongue height (TGH) was measured. Data were analyzed by one-way and two-way ANOVA, Tukey tests, and Pearson's and Spearman's correlation tests (α=0.05).
Results: The volume of the LNP was significantly larger in Class II compared to Class III patients ($P<0.05$). VLP volume ($r>0.5$, $P<0.05$) and TV ($r>0.5$, $P<0.05$) in Class I high angle participants had a significant correlation with D1.
Conclusion: The results showed greater LNP volume in Class II compared to Class III individuals. In some variables (VLP, ORP, TV, intraoral airway volume), no significant difference was observed between sagittal and vertical groups. Most airway variables (TV, VLP, and ORP) had no correlations with some tongue variables (TGH, D1, D3, D4, D4', D5, and intraoral airway volume) in different skeletal patterns.

Keywords: Cone-Beam Computed Tomography, Skeletal Pattern, Tongue Posture, Upper Pharyngeal Airway Volume.

Background

The biological principles of orthodontics are mainly limited to the hard tissue structures such as bone and teeth. A review of the scientific orthodontic literature reveals that the current understanding of soft tissue forces and oral muscle balance has been poorly developed (1). Since the tongue plays a vital role in the development of dental and skeletal malocclusions, its position should be considered in orthodontic and orthopedic treatment planning (2).

The relationship between craniofacial morphology and respiratory system function was noticed for the first time in the late nineteenth century (3). Evidence shows that a mutual correlation may exist between different facial growth patterns and the pharyngeal airway volume

Copyright © 2023, Author(s). This is an open-access article distributed under the terms of the Creative Commons Attribution-NonCommercial 4.0 International License (http://creativecommons.org/licenses/by-nc/4.0/) which permits copy and redistribute the material just in noncommercial usages, provided the original work is properly cited.

(4–7). Airway obstruction can adversely affect and change the nasal respiratory function, resulting in craniofacial and tooth position anomalies (8,9). It has been reported that differences in oropharyngeal airway dimensions in individuals with different skeletal patterns may be due to their different tongue positions (10–12).

A previous two-dimensional study on the correlation between tongue position at rest and different skeletal patterns revealed no significant correlation in this regard (1). However, some other studies showed an average higher tongue position at rest in Class II (Cl II) individuals (13,14). Also, higher tongue position has been reported in individuals with a vertical growth pattern (15,16). Nonetheless, another study reported lower tongue position at rest in individuals with vertical growth patterns (17).

Considering the existing controversy in the results of 2D studies on this relationship, cone-beam computed tomography (CBCT), as a 3D imaging modality, was recently used to address this relationship more accurately. Accordingly, some studies showed larger tongue volume in Class III (Cl III) (18) and lower tongue position in Cl II individuals (19,20). Another study indicated that anterior tongue position significantly correlated with mandibular protrusion (20).

The majority of the available studies have indicated a lack of a significant correlation between the upper pharyngeal airway volume and different skeletal patterns (13,20–25). Other studies demonstrated larger dimensions of the oropharynx in Cl III individuals (23,26), while another study showed significantly smaller nasopharyngeal volume in Cl II patients (24). It was also reported that upper pharyngeal airway volume in individuals with a vertical growth pattern was narrower than in individuals with a horizontal growth pattern (16,17).

Studies addressing the correlation of tongue position at rest and airway volume in different skeletal patterns three-dimensionally are limited. Moreover, the sample size and mean age of participants in the available studies on this topic have been low, and mainly children have been evaluated during their growth period. Considering the existing controversy and the possible effect of tongue position on upper pharyngeal airway dimensions, this study assessed the relationship between upper pharyngeal airway volume and tongue position in different sagittal and vertical skeletal patterns using CBCT.

Methods

This cross-sectional study was conducted on 225 CBCT scans taken between 2016 and 2021, retrieved from the archives of two oral and maxillofacial radiology centers. All the participants consented to using their imaging data for research purposes. The study protocol was approved by the Ethics Committee of Shahid Beheshti University of Medical Sciences (IR.SBMU.DRC.REC.1400.036). All the CBCT scans were obtained for diagnostic or treatment-planning purposes unrelated to this study.

Sample size

The sample size was calculated at n=30 in each group assuming α=0.05, β=0.2, study power of 80%, and effect size of 0.5. A total of 225 CBCT scans were selected from the initial sample of 609 after applying the eligibility criteria.

Eligibility criteria

The inclusion criteria were (I) age over 18 years, (II) complete eruption of permanent anterior teeth and second premolars, and presence of at least one first and one second molar in each jaw, and (III) the tongue had to be at rest and not in full contact with the palate during CBCT scanning.

The exclusion criteria were (I) patients with a history of orthodontic or orthopedic treatment, (II) the presence of dental or craniofacial anomalies, and (III) syndromic patients and those with a history of trauma to the maxillofacial region.

Imaging protocol

Imaging had been performed according to the standard protocol for all the participants. During scanning, the patients were requested not to move, not to swallow their saliva, and to keep their tongue at rest. All CBCT scans were taken with exposure settings of 80 kV, maximum amperage of 2 mA, exposure time of 17 seconds, and a 0.39-mm voxel size.

Measurements

For the measurements, the images (DICOM files) were reconstructed in the coronal, axial, sagittal, and 3D sections by OnDemand 3D software (CyberMed; File version: 1.0.10.6388; date created: 2017). A total of 229 axial slices with 0.78-mm slice thickness were assessed for each patient. The age and sex of patients, their skeletal measurements, length, height and position of their tongue, and upper pharyngeal airway volume were recorded for each patient.

Skeletal landmarks

From the View menu, the Volume of Interest Overlay was selected. On the coronal view, the right half of the patient was omitted. Cephalometric landmarks and reference planes were then identified for the measurements, as described in Table 1.

Table 1. Cephalometric landmarks and reference planes used for the measurements

Measurements	Description
ANS	The most anterior point on the sharp appendage of the maxilla in the lower part of the anterior nostril
EB	Base of epiglottis
Go	A point on the curvature of the angle of the mandible, which is formed by the bisector of the tangent lines on the lower edge of the mandible and the posterior edge of the ramus.
Gn	The point in the middle of the Pogonion point and the Menton point
Me	The lowest point in the symphysis of the mandible
N	The most anterior point at the intersection between the frontal and nasal bones in the midsagittal plane
PNS	The posterior spine of the palatine bone that forms part of the hard palate
Point A	The most posterior point in the concavity of the middle part of the face in the maxilla between the ANS and the prosthion
Point B	The most posterior point is in the middle part of the mandibular cavity, which is between the pogonion and the infradental
S	Sella turcica geometric center
TT	The most anterior point of the tongue
Ba	The lowest point on the anterior edge of the foramen magnum
So	Midpoint of the sella-basion line
Ad1	The intersection of the PNS- Ba line and the posterior wall of the nasopharyngeal airway
Ad2	The intersection of the PNS-So line and the posterior wall of the nasopharyngeal airway
T2	Intersection between tongue contour and occlusal plane
P3	The junction between the posterior pharyngeal wall and the occlusal plane
E	The uppermost point of the epiglottis
E1	The anterior wall of the pharyngeal airway is on the E1-E2 line, which is a line parallel to the occlusal plane
E2	The posterior wall of the pharyngeal airway is on the E1-E2 line
Functional occlusal plane	The line connecting the meeting place of the cusps of the first molar to the meeting place of the cusps of the first premolar

Skeletal analyses

The participants were evaluated in three groups with sagittal Class I, II, and III skeletal patterns. Class I(Cl I) and II individuals were subdivided into three vertical subgroups: high angle, normal, and low angle. The following skeletal analyses were used for Clifications (1):

The Jarabak ratio: posterior facial height/anterior facial height ×100, and values between 62% and 65% indicated normal, values >65% indicated low angle, and values <62% indicated high angle.

SN-MeGo: Values between 28.5° and 39.5° indicated normal, values >39.5° indicated high angle, and values <28.5° indicated low angle.

ANB: Cl 1: 0–4°, Cl 2: >4°, Cl 3: <0°.

Tongue position analyses

Tongue length (TGL): The distance between the base of the epiglottis (EB) and tongue tip (TT) was measured on the mid-sagittal section in the sagittal plane in x-ray mode and reported in millimeters (Fig. 1A).

Tongue height (TGH): The length of the vertical bisection from the dorsal surface of the tongue to the line connecting the base of the epiglottis and TT was measured on the mid-sagittal section in the sagittal plane in x-ray mode and reported in millimeters (Fig. 1A).

Tongue position (Graber analysis): A horizontal line was drawn from the incisal edge of the lower central incisor to the cervical third of the distal surface of the second molar on the mid-sagittal section in the 3D view. The selected point at the cervical third of the distal surface of the second molar was considered the center point from which 30-, 60-, 90-, 120-, and 150-degree angles were drawn. The distances between the distal surface of the second molar and the tongue contour (D1-D5 lines) and from the tongue contour to the palate were measured at these points (D1'-D5') (Fig. 1B).

Upper pharyngeal airway volume measurements

Lower nasopharynx (LNP) volume: This part of the airway was confined to the Ad2-PNS line superiorly and the Ad1-PNS line inferiorly. Its volume was measured in the 3D view in airway mode (Fig. 2A).

Velopharynx (VLP) volume: This part of the airway was confined to the Ad1-PNS line superiorly and the T2-P3 line inferiorly. Its volume was measured in the 3D view in airway mode (Fig. 2A).

Oropharynx (ORP) volume: This part of the airway was confined to the T2-P3 line superiorly and the E1-E2 line inferiorly. Its volume was measured in the 3D view in airway mode (Fig. 2).

Total volume (TV) of the upper airways: This area was confined to the Ad2-PNS line superiorly and the E1-E2 line inferiorly. Its volume was measured in the 3D view in airway mode (Fig. 2A).

Intraoral airway volume: The intraoral airway volume was also measured, as shown in Fig. 2B.

Reliability of measurements

One trained and calibrated dental student made all the measurements on the anonymous CBCT images. The anatomical points and landmarks on 20 randomly selected images were remeasured by an orthodontist, and the inter-examiner reliability was calculated. Also, 20 CBCT scans were randomly selected and remeasured by the examiners after a 2-week interval to calculate intra-examiner reliability. The level of agreement was calculated using the intraclass correlation coefficient (ICC) and paired t-test.

Statistical analysis

Data were analyzed using SPSS 20 (SPSS Inc., IL, USA). Considering the normal distribution of data as confirmed by the Kolmogorov-Smirnov test ($p>0.05$) and homogeneity of variances as confirmed by Levene's test ($p>0.05$), one-way ANOVA was applied to compare upper pharyngeal airway variables between the three sagittal skeletal classes followed by HSD Tukey tests for pairwise comparisons. Two-way ANOVA was used to compare upper pharyngeal airway variables among patients with six different sagittal skeletal and vertical patterns. The correlation between the upper pharyngeal airway variables and tongue variables was analyzed using Pearson's and Spearman's correlation coefficients. Statistical significance was set at $P<0.05$.




Figure 1. Measurements of the tongue dimensions and position: (A) TGL and TGH measurements; (B) assessment of tongue position on the 3D view in x-ray and R modes (red lines: D1-D5, yellow lines: D1'-D5').




Figure 2. (A) Volume of the upper pharyngeal airway was measured in three parts using the anatomical landmarks: lower nasopharynx (LNP; yellow), velopharynx (VLP, blue), and oropharynx (ORP, red); **(B)** measurement of intraoral airway volume.

Results

CBCT images of 149 females (66.12%) and 76 males (33.8%) were evaluated. The mean age of the participants was 33.06±10.77 years (range: 18–77 years). A total of 100 patients had Cl I, 100 had Cl II, and 25 had Cl III skeletal patterns. Of 100 Cl I patients, 37 were low angle, 33 were normal, and 30 were high angle. Of 100 Cl II patients, 36 were low angle, 33 were normal, and 31 were high angle.

Results of reliability assessment

The ICC value was 1 (95% CI: 0.99–1) for intra-examiner reliability and 0.998 (95% CI: 0.99–1) for inter-examiner reliability. The paired t-test showed a mean difference of 0.06±0.50 for intra-examiner reliability (P=0.400) and 0.01±0.85 for inter-examiner reliability (P=0.939), indicating no significant differences between the two measurements.

Results of airway measurements

Table 2 presents the mean airway dimensions measured in the three sagittal skeletal classes. Significant differences were noted in Go-Gn (P=0.000) and LNP (P=0.046) between the three classes. Thus, pairwise comparisons were carried out (Table 3), which showed significantly higher LNP volume in Cl II compared to Cl III individuals (P=0.045). Also, the Go-Me length in Cl III individuals was greater than that in Cl I individuals (P=0.001). Go-Me length in Cl I individuals was significantly greater than in Cl II patients (P=0.017). No other significant differences were noted.

Table 4 presents the measured airway dimensions in different sagittal and vertical skeletal patterns. Two-way ANOVA showed no significant difference in LNP, VLP, ORP, TV, and intraoral airway volume between the vertical and sagittal groups and their interactions (P>0.05).

Correlation of tongue position and airway dimensions in different sagittal skeletal patterns:

As shown in Table 5, VLP volume in Cl II patients showed a low inverse correlation with TGH (r=-0.224, P=0.025). ORP volume in Cl I individuals showed a low inverse correlation with D4 (r=-0.237, P=0.018) and D5 (r=-0.254, P=0.011). In the Cl III group, ORP volume had a low correlation with D3 (r=0.404, P=0.045). TV had a low inverse correlation with TGH in Cl II patients (r=-0.211, P=0.035).

Table 2. Mean airway dimensions measured in the three sagittal skeletal classes

Related variables	Sagittal skeletal pattern	Mean	SD	P-value*
Go-Gn	Cl I	73.64	4.76	0.000*
	Cl II	71.64	5.24	
	Cl III	77.93	6.12	
	Total	73.23	5.46	
LNP	Cl I	3.82	1.39	0.046*
	Cl II	3.82	1.44	
	Cl III	3.04	1.53	
	Total	3.72	1.44	
VLP	Cl I	5.25	2.48	0.927
	Cl II	5.38	2.63	
	Cl III	5.40	2.55	
	Total	5.33	2.54	
ORP	Cl I	5.14	2.04	0.646
	Cl II	5.41	2.58	
	Cl III	5.50	2.07	
	Total	5.30	2.29	
TV	Cl I	14.01	4.87	0.757
	Cl II	14.48	5.57	
	Cl III	13.81	4.86	
	Total	14.19	5.18	
Intraoral airway volume	Cl I	1.28	2.11	0.466
	Cl II	0.94	1.82	
	Cl III	1.28	2.25	
	Total	1.13	2.00	

*Significant based on the One-way ANOVA

Table 3. Pairwise comparisons of skeletal classes regarding LNP and G-Gn length by HSD Tukey tests

Related variables	Sagittal skeletal pattern	Sagittal skeletal pattern	Mean difference	P-value
LNP	Cl I	Cl II	0.02527-	0.991
		Cl III	0.74579	0.054
	Cl II	Cl III	0.77106	0.045*
Go-Gn	Cl I	Cl II	2.00540	0.017*
		Cl III	4.28560-	0.001*
	Cl II	Cl III	6.29100-	<0.001*

*Significant based on the One-way ANOVA

Table 4. Measured airway dimensions in different sagittal and vertical skeletal patterns

Related variables	Sagittal skeletal patterns	Vertical skeletal patterns	Mean	Std. deviation
Go-Gn	Cl I	High angle	73.50	5.04
		normal	73.87	4.59
		Low angle	73.40	4.79
	Cl II	High angle	70.78	4.10
		Normal	71.25	4.68
		Low angle	72.74	6.43
LNP	Cl I	High angle	3.48	1.24
		Normal	3.93	1.53
		Low angle	3.92	1.38
	Cl II	High angle	4.09	1.61
		Normal	3.60	1.10
		Low angle	3.78	1.55
VLP	Cl I	High angle	4.82	2.16
		Normal	4.46	2.61
		Low angle	5.43	2.61
	Cl II	High angle	5.01	2.33
		Normal	5.52	2.79
		Low angle	5.58	2.75
ORP	Cl I	High angle	5.02	1.90
		Normal	5.05	2.09
		Low angle	5.31	2.14
	Cl II	High angle	5.23	2.17
		normal	5.27	2.76
		Low angle	5.67	2.78
TV	Cl I	High angle	13.16	4.53
		normal	14.28	4.96
		Low angle	14.45	5.11
	Cl II	High angle	14.21	4.92
		normal	14.27	5.50
		Low angle	14.89	6.24
Intraoral airway volume	Cl I	High angle	1.50	2.07
		normal	0.95	2.03
		Low angle	1.39	2.23
	Cl II	High angle	1.56	2.74
		normal	0.79	1.28
		Low angle	0.55	0.97

Table 5. Correlation of tongue position and airway dimensions in different sagittal skeletal patterns

Airway variables	Sagittal skeletal patterns		TGH	D3	D4	D5
LNP	Cl I	Correlation Coefficient	-0.81	0.107	-0.033	-0.032
		p-value	0.420	0.289	0.474	0.751
	Cl II	Correlation Coefficient	-0.186	-0.125	-0.166	-0.160
		p-value	0.065	0.216	0.099	0.112
	Cl III	Correlation Coefficient	-0.317	-0.332	-0.272	-0.309
		p-value	0.122	0.105	0.189	0.133
VLP	Cl I	Correlation Coefficient	-0.076	0.062	-0.119	-0.115
		p-value	0.452	0.539	0.239	0.253
	Cl II	Correlation Coefficient	*-0.224	0.064	-0.095	-0.105
		p-value	*0.025	0.527	0.347	0.297
	Cl III	Correlation Coefficient	0.000	0.117	0.163	0.082
		p-value	0.998	0.576	0.435	0.699
ORP	Cl I	Correlation Coefficient	0.138	0.034	*0.237-	-0.254*
		p-value	0.171	0.735	*0.018	0.011*
	Cl II	Correlation Coefficient	-0.128	-0.006	-0.105	-0.065
		p-value	0.203	0.954	0.299	0.522
	Cl III	Correlation Coefficient	0.358	*0.404	0.255	0.106
		p-value	0.079	*0.045	0.218	0.614
TV	Cl I	Correlation Coefficient	-0.005	0.076	-0.175	-0.179
		p-value	0.958	0.452	0.081	0.074
	Cl II	Correlation Coefficient	*0.211-	-0.003	-0.133	-0.120
		p-value	*0.035	0.976	0.185	0.234
	Cl III	Correlation Coefficient	0.068	0.136	0.110	-0.010
		p-value	0.748	0.516	0.599	0.961

*Significant

Correlation of tongue position and airway variables with Go-Gn

A weak correlation was found between ORP volume and Go-Gn in Cl I (r=0.299, P=0.002) and Cl II (r=0.208, P=0.038) participants, but not in the Cl III group.

Correlation of tongue position and airway variables in different sagittal and vertical skeletal patterns

LNP volume: No significant correlations were noted in this regard.

VLP volume: In Cl I high angle participants, a moderate correlation was found between VLP volume and D1 (r=0.514, P=0.004). In the Cl I normal group, a low correlation was found between VLP volume and D4' (r=0.441, P=0.008), VLP volume, and intraoral airway volume (r=0.441, P=0.010). In the Cl II low angle group, a low inverse correlation was noted with D4' (r=-0.385, P=0.020).

ORP volume: In the Cl I high angle group, a weak correlation was noted between ORP volume and D1 (r=0.472, P=0.004).

TV: In the Cl I high angle group, a moderate correlation was found between TV and D1 (r=0.528, P=0.003). In the Cl I normal group, a weak correlation was found between TV and D4' (r=0.463, P=0.007). In the Cl II normal group, a small inverse correlation was found between TV and D5 (r=-0.357, P=0.042).

No other significant correlations were found (P>0.05).

Correlation of pharyngeal airway variables with Go-Gn in different sagittal and vertical skeletal patterns

In the Cl I high angle group, a weak correlation was noted between Go-Gn and VLP volume (r=0.419, P=0.021), ORP volume (r=0.441, P=0.015), and TV (r=0.438, P=0.016). No other significant correlations were found (P>0.05).

Discussion

This study assessed the relationship of upper pharyngeal airway volume with tongue position in different sagittal and vertical skeletal patterns using CBCT. The results showed no significant differences in the TV of the airways between different sagittal groups, which was in line with the findings of Di Carlo et al. (22), who assessed the correlation of upper airway volume with different craniofacial patterns (Cl I, II, and III). This result also coincided with the findings of Alves et al. (25), who evaluated the upper airway volume in Cl II and Cl III patients using CBCT, and El and Palomo (26), who evaluated airway dimensions in patients with different sagittal positions of the maxilla and mandible.

In the present study, the LNP volume in Cl II individuals was larger than that in the Cl III group, while the difference between Cl I and II groups was not significant. This finding differs from the results reported Di Carlo et al. (22), who found no

significant difference in the volume of the nasopharynx between different groups. This difference in the results of the two studies might be because individuals over 18 were included in the present study, while the study population in the study by Di Carlo et al. (22) also included adolescents in their growth period (13 to 43 years). This difference in the results might indicate that the airway growth pattern may change with age, and growth and development can affect this pattern. The present results differ from the findings of El and Palomo (26), who showed smaller nasopharyngeal airway dimensions in skeletal Cl II patients compared with the Cl I group. The nasal volume in their study included the nasopharynx, conchae, and nares, while in the present study, the volume of the lower part of the nasopharynx was measured, possibly explaining the discrepancies in the results. Larger LNP volume in Cl II patients can be attributed to the forward position of the maxillary complex.

In the present study, the VLP volume was not significantly different in individuals with different skeletal patterns, which is consistent with the results of Di Carlo et al. (22) and different from the findings of Claudino et al. (27), who showed smaller VLP volume in Cl II than in Cl III and Cl I groups. Their sample size was smaller than in the present study, and they used the uvula as the lower extension of the VLP, while the functional occlusal line was used as a reference for the lower extension of the VLP in the current study (16). Moreover, Iranian patients were assessed in the present study. These factors can explain the variations in the results.

In the present study, the ORP volume was not significantly different between different skeletal patterns, which is in line with the results of Alves et al. (25) and Memon et al. (28) and in contrast to the findings of El and Palomo (26). The latter study showed that the ORP volume was smaller in patients with a retruded mandible. This difference can be attributed to their small sample size. Nonetheless, a positive correlation was found between the mandibular length and ORP volume in Cl I and II groups, consistent with the results of Alves et al. (29) and El and Palomo (26).

In the present study, no significant difference was found in the upper pharyngeal airway volume in different vertical subgroups, consistent with the findings of Grauer et al. (30), who assessed the form and volume of the upper pharyngeal airways and their correlation with facial morphology by CBCT. However, this finding is in contrast to the findings of Tarkar et al. (16), de Freitas et al. (31), and Ucar and Uysal (17). They all showed that individuals with vertical growth patterns had narrower upper airway dimensions than those with horizontal growth patterns. This difference can be because previous studies assessed the airway dimensions two-dimensionally.

The intraoral airway volume was not significantly different in different skeletal patterns in the present study, consistent with the findings of Iwasaki et al. (20), who found no significant difference in the intraoral airway volume between Cl I, II, and III groups.

In the present study, the VLP volume, ORP volume, and TV had low to moderate correlations with some variables related to the tongue position (TGH, D1, D3, D4, D4', D5, and intraoral airway volume) in some skeletal groups. This finding is consistent with the results of Battagel et al. (10), who showed that the hyoid bone and its muscular system play a key role in pharyngeal airway volume, and the position of the mandible and tongue affect the position of the hyoid bone. Thus, tongue position can affect the pharyngeal airway volume.

In the present study, an inverse correlation was noted between VLP volume and TV with TGH, which can indicate the effect of increased TGH in reduction of airway volume and decreased respiratory function. An increase in TGH shifts the hyoid bone with the attached tongue muscles (genioglossus and geniohyoid) backward. As a result, the VLP volume decreases, reducing the airway TVs.

In the present study, a weak correlation was observed between the mandibular length and ORP volume in Cl I and II groups, consistent with the findings of Diwakar et al. (32) and Trenouth and Timms (33). One possible reason may be that increased mandibular length increases the genioglossus and geniohyoid muscle attachments moving forward and farther from the muscles, increasing ORP volume.

In the present study, the majority of variables related to the tongue position (TGL, D1', D2, D2', D3', and D5') exhibited no significant correlation with airway variables. The reason may be that although patients were asked to keep their tongue at a resting position, the distance between the tongue and palate was minimal in most cases and the oral volume was filled with the tongue almost completely.

Assessment of both the sagittal and vertical dimensions, larger sample size compared with previous investigations (18), and optimally high intra- and inter-examiner reliability were among the strengths of the present study.

This study had some limitations as well. The tongue position in most cases was such that the residual air volume was too small, and since the tongue position can easily change, the results may

not have sufficient reliability and reproducibility.

Future studies must find a reliable method for assessing tongue position on CBCT scans. Sagittal skeletal patterns can also be divided into smaller subgroups to determine which jaw is responsible for malocclusion, and the relationship of these subgroups should be assessed with the airway volume. Moreover, airway volume should be compared between individuals in different age groups.

Conclusion

The present study showed greater LNP volume in Cl II than in Cl III individuals. In some variables (VLP, ORP, TV, intraoral airway volume), no significant difference was observed between different sagittal and vertical groups. Most airway variables (TV, VLP, ORP) did not correlate with some tongue variables (TGH, D1, D3, D4, D4', D5, and intraoral airway volume) in different skeletal patterns.

Acknowledgment

The present article was extracted from a thesis for an undergraduate degree in dentistry, entitled "Relationship of upper pharyngeal airway volume and tongue position in different skeletal patterns: A CBCT study," at the Shahid Beheshti University of Medical Sciences, Tehran, Iran. The study protocol was approved by the institutional Ethics Committee under the code IR.SBMU.DRC.REC.1400.036. The budget for this study was provided by the School of Dentistry, the Shahid Beheshti University of Medical Science.

Conflicts of interest: None to declare.

References

1. Fatima F, Fida M. The assessment of resting tongue posture in different sagittal skeletal patterns. Dental Press J Orthod. 2019;24(3):55-63. doi: 10.1590/2177-6709.24.3.055-063.oar.
2. Sainath MC, Vimala G, Kalam RAA. Baseline Tongue Parameters in Normodivergent Skeletal Class I South Indian Subjects. J Indian Orthod Soc. 2013;47(6):343-7. doi:10.5005/jp-journals-10021-1184.
3. Meyer W. On Adenoid Vegetations in the Naso-pharyngeal Cavity: their Pathology, Diagnosis, and Treatment. Med Chir Trans. 1870;53:191-216.1. doi: 10.1177/095952877005300110.
4. Bresolin D, Shapiro PA, Shapiro GG, Chapko MK, Dassel S. Mouth breathing in allergic children: its relationship to dentofacial development. Am J Orthod. 1983;83(4):334-40. doi: 10.1016/0002-9416(83)90229-4.
5. Kerr WJ. The nasopharynx, face height, and overbite. Angle Orthod. 1985;55(1):31-6. doi: 10.1043/0003-3219(1985)055<0031:TNFHAO>2.0.CO;2.
6. Lee YS, Kim JC. A cephalometric study on the airway size according to the types of the malocclusion. Korean J Orthod. 1995;25(1):19-29.
7. McNamara JA. Influence of respiratory pattern on craniofacial growth. Angle Orthod. 1981;51(4):269-300. doi: 10.1043/0003-3219(1981)051<0269:IORPOC>2.0.CO;2.
8. Joseph AA, Elbaum J, Cisneros GJ, Eisig SB. A cephalometric comparative study of the soft tissue airway dimensions in persons with hyperdivergent and normodivergent facial patterns. J Oral Maxillofac Surg. 1998;56(2):135-9; discussion 139-40. doi: 10.1016/s0278-2391(98)90850-3.
9. Tourne LP. The long face syndrome and impairment of the nasopharyngeal airway. Angle Orthod. 1990;60(3):167-76. doi: 10.1043/0003-3219(1990)060<0167:TLFSAI>2.0.CO;2.
10. Battagel JM, Johal A, Kotecha B. A cephalometric comparison of subjects with snoring and obstructive sleep apnoea. Eur J Orthod. 2000;22(4):353-65. doi: 10.1093/ejo/22.4.353.
11. Lowe AA, Fleetham JA, Adachi S, Ryan CF. Cephalometric and computed tomographic predictors of obstructive sleep apnea severity. Am J Orthod Dentofacial Orthop. 1995;107(6):589-95. doi: 10.1016/s0889-5406(95)70101-x.
12. Miles PG, Vig PS, Weyant RJ, Forrest TD, Rockette HE Jr. Craniofacial structure and obstructive sleep apnea syndrome--a qualitative analysis and meta-analysis of the literature. Am J Orthod Dentofacial Orthop. 1996;109(2):163-72. doi: 10.1016/s0889-5406(96)70177-4 .
13. Chauhan A, Autar R, Pradhan KL, Yadav V. Comparison of pharyngeal airway dimension, tongue and hyoid bone position based on ANB angle. Natl J Maxillofac Surg. 2015;6(1):42-51. doi: 10.4103/0975-5950.168237.
14. Primozic J, Farcnik F, Perinetti G, Richmond S, Ovsenik M. The association of tongue posture with the dentoalveolar maxillary and mandibular morphology in Class III malocclusion: a controlled study. Eur J Orthod. 2013;35(3):388-93. doi: 10.1093/ejo/cjs015.
15. Subrahmanya RM, Gupta S. Assessment and comparison of tongue posture in individuals with different vertical facial patterns. J Orofac Res. 2014:4(2): 67-71.
16. Tarkar JS, Parashar S, Gupta G, Bhardwaj P, Maurya RK, Singh A, Singh P. An Evaluation of Upper and Lower Pharyngeal Airway Width, Tongue Posture and Hyoid Bone Position in Subjects with Different Growth Patterns. J Clin Diagn Res. 2016;10(1): ZC79-83. doi: 10.7860/JCDR/2016/16746.7158.
17. Ucar FI, Uysal T. Orofacial airway dimensions in subjects with Class I malocclusion and different growth patterns. Angle Orthod. 2011;81(3):460-8. doi:10.2319/091910-545.1 .
18. Iwasaki T, Suga H, Yanagisawa-Minami A, Sato H,

Sato-Hashiguchi M, Shirazawa Y, Tsujii T, Yamamoto Y, Kanomi R, Yamasaki Y. Relationships among tongue volume, hyoid position, airway volume and maxillofacial form in paediatric patients with Class-I, Class-II and Class-III malocclusions. Orthod Craniofac Res. 2019;22(1):9-15. doi: 10.1111/ocr.12251.

19. Chen W, Mou H, Qian Y, Qian L. Evaluation of the position and morphology of tongue and hyoid bone in skeletal Class II malocclusion based on cone beam computed tomography. BMC Oral Health. 2021;21(1):475. doi: 10.1186/s12903-021-01839-y.
20. Iwasaki T, Sato H, Suga H, Takemoto Y, Inada E, Saitoh I, Kakuno E, Kanomi R, Yamasaki Y. Relationships among nasal resistance, adenoids, tonsils, and tongue posture and maxillofacial form in Class II and Class III children. Am J Orthod Dentofacial Orthop. 2017;151(5):929-940. doi: 10.1016/j.ajodo.2016.10.027.
21. Brito FC, Brunetto DP, Nojima MCG. Three-dimensional study of the upper airway in different skeletal Class II malocclusion patterns. Angle Orthod. 2019;89(1):93-101. doi: 10.2319/112117-806.1.
22. Di Carlo G, Polimeni A, Melsen B, Cattaneo PM. The relationship between upper airways and craniofacial morphology studied in 3D. A CBCT study. Orthod Craniofac Res. 2015;18(1):1-11. doi: 10.1111/ocr.12053 .
23. Indriksone I, Jakobsone G. The upper airway dimensions in different sagittal craniofacial patterns: a systematic review. Stomatologija. 2014;16(3):109-17 .
24. Zheng ZH, Yamaguchi T, Kurihara A, Li HF, Maki K. Three-dimensional evaluation of upper airway in patients with different anteroposterior skeletal patterns. Orthod Craniofac Res. 2014;17(1):38-48. doi: 10.1111/ocr.12029.
25. Alves PV, Zhao L, O'Gara M, Patel PK, Bolognese AM. Three-dimensional cephalometric study of upper airway space in skeletal class II and III healthy patients. J Craniofac Surg. 2008;19(6):1497-507. doi: 10.1097/SCS.0b013e31818972ef.
26. El H, Palomo JM. An airway study of different maxillary and mandibular sagittal positions. Eur J Orthod. 2013;35(2):262-70. doi: 10.1093/ejo/cjr114 .
27. Claudino LV, Mattos CT, Ruellas AC, Sant' Anna EF. Pharyngeal airway characterization in adolescents related to facial skeletal pattern: a preliminary study. Am J Orthod Dentofacial Orthop. 2013;143(6):799-809. doi: 10.1016/j.ajodo.2013.01.015.
28. Memon S, Fida M, Shaikh A. Comparison of different craniofacial patterns with pharyngeal widths. J Coll Physicians Surg Pak. 2012;22(5):302-6.
29. Alves M Jr, Franzotti ES, Baratieri C, Nunes LK, Nojima LI, Ruellas AC. Evaluation of pharyngeal airway space amongst different skeletal patterns. Int J Oral Maxillofac Surg. 2012;41(7):814-9. doi: 10.1016/j.ijom.2012.01.015 .
30. Grauer D, Cevidanes LS, Styner MA, Ackerman JL, Proffit WR. Pharyngeal airway volume and shape from cone-beam computed tomography: relationship to facial morphology. Am J Orthod Dentofacial Orthop. 2009;136(6):805-14. doi: 10.1016/j.ajodo.2008.01.020 .
31. de Freitas MR, Alcazar NM, Janson G, de Freitas KM, Henriques JF. Upper and lower pharyngeal airways in subjects with Class I and Class II malocclusions and different growth patterns. Am J Orthod Dentofacial Orthop. 2006;130(6):742-5. doi: 10.1016/j.ajodo.2005.01.033.
32. Diwakar R, Kochhar AS, Gupta H, Kaur H, Sidhu MS, Skountrianos H, Singh G, Tepedino M. Effect of Craniofacial Morphology on Pharyngeal Airway Volume Measured Using Cone-Beam Computed Tomography (CBCT)-A Retrospective Pilot Study. Int J Environ Res Public Health. 2021;18(9):5040. doi:10.3390/ijerph18095040.
33. Trenouth MJ, Timms DJ. Relationship of the functional oropharynx to craniofacial morphology. Angle Orthod. 1999;69(5):419-23. doi: 10.1043/0003-3219(1999)069<0419:ROTFOT>2.3.CO;2.